



Perforated Pup joints are installed in completion string for bypass of flow if downhole gauges are ran for pressure/temperature monitoring. The holes are perforated while ensuring the joint integrity along with cross-sectional area at-least equivalent to relevant tubing internal diameter.

## **Features**

- Comes with variety of different thread types (API/ Proprietary) and thread size combinations
- Complies with API 5CT
- Reliable and proven

## **Options**

- Various sizes, different threading & different materials are available.
- OD will vary with tubing weight and thread type.
- Connection type as per requirement

